

#### STATE OF ALABAMA

## ALABAMA HISTORICAL COMMISSION 725 MONROE STREET MONTGOMERY, ALABAMA 36130 PHONE: 832-6621



### ALABAMA REGISTER OF LANDMARKS AND HERITAGE Nomination Form

COUNTY Baldwin	
NAME: Present (None) Mª Noir House Hist	toric Sunnyside Hotel
LOCATION: Street and Number Northwest corner of	Oak and Jessamine Streets
Town (Give directions if rural) Magn	olia Springs, Alabama 36555
*A MAP WITH THE LANDMARK MARKED MUST BE SUE	MITTED WITH THIS FORM*
CATEGORY: Building ( ) Structure ( ) Object	( ) Site ( ) District ( )
USE: Present Private residence Hist	coric Hotel
OWNERSHIP: Public ( ) Private ( x )	
Owner's Name Donald W. and Rita H.	McNair
Mailing Address _ Box 173	
	bama 36555
INTEGRITY: Original Site (X) Moved () When	1?
From where?	(Give details in significance.)
CONDITIONS: Excellent ( $\chi$ ) Good ( ) Fair (	
THREATS: No ( *) Yes ( ) By What?	
RESTORATION WORK: Being considered ( ) Underway	( ) Completed ( X ) Not planned ( )
SURROUNDING ENVIRONMENT: Open land ( ) Woodland High building density ( Residential ( X ) Rural	) Commercial ( ) Industrial ( )
Acreage Less than one	

For all categories other than a district and object give a site plan with a North arrow. Show related buildings.

For a district give a verbal boundary description and attach a sketch map of the district.

SIGNIFICANCE:	
Why is this landmark significant?	<pre>(χ) associated with events, persons, or movements</pre>
healthy mineral waters from the springs vacationers at the turn of the century a	area housed prospective buyers here. Good hunting, and beautiful surroundings attracted many wealthy and after; many who vacationed at the Sunnyside stayed rings. (See photocopy of Magnolia Plaza sales brochure major importance.
Not Known	
people and events associated with to The property is first recorded in McLennan purchased property 7/31/1897; and newspaper articles date house as been property for \$3500 on 11/14/13 and on 11 financed the property. The Hardings randeveloped most of Magnolia Springs in the prospective property buyers. Sometime of Hardings, either as a gift or in lieu of was Mrs. Hardings sister) who had come to continued to board guests and serve mean the 20's he served as a guide for a grow State sources of information, givin Real Estate Records - Judge of Probate, 1925; Photos, writings and Post Cards of Association; Interviews with local resi	of the Landmark. Include information on important he landmark. (USE ADDITIONAL SHEETS IF NECESSARY)  1894 as Lot \$\frac{1}{2}\$ of the 0.S. Lyman subdivision. Christopher sold to Edwin A. Bemis 11/21/1900. Local historians ing built in 1897 or 1898. W.H. Harding purchased 1/15/13 title was conveyed to Frank H. Brunell who in the Sunnyside Hotel for many years. Mr. Brunell he '20's and 30's and used the Sunnyside as lodgings for during this period, the property was deeded to the f salary. At their death it passed to the Cowan's (she to help them run the Hotel in the summer of 1920. They is until the 40's. Mr. G. Bernard tells us that during up of wealthy Chicago sportsmen who stayed for 3 months is full bibliographical data: (continued)  Baldwin County, AL.; Magnolia Plaza sales brochure of f local historians; Minutes of Magnolia Springs Community dents (we had an Open House after restoration and everyappeared in many newspaper articles over the years.
Complete as directed below for each	category.
BUILDING:	
Number of stories F	Toundation Brick Basement
Wall Material: (Note changes from (clapboard, brick, wood or brick, met	stone, wood shingle, board and batton, stucco over
Clapboard of heart of yellow pine.	

Structural System: (If known)
Wood frame (X ) Load-bearing masonry ( ) Iron or Steel ( )

# HISTORY OF THE LANDMARK (Continued)

each winter, bringing their own whiskey in a wagon load of trunks. He tells us that by then, guests traveled as far as Foley by train and came the rest of the way by wagon. In the early 1900's guests arrived by boat (the dock is at the

foot of Jessamine St.).

The Sunnyside also served as Magnolia Springs major meeting place and eating spot. Mrs. Challenor, daughter of the late Dr. Howe, states that he attended many a dinner in the dining room during the early 1900's. As the areas only doctor he was a dignitary on everyones list. It continued to be a popular spot for Sunday dinner for local residents until sometime in the late 40's or early 50's. Local Creole familes have told us the Sunnyside was known for good fish and purchased a good portion of their catch. We have talked to several Creoles who worked here and they all tell us the meals were served at one very long table that ran the length of the 31 foot dining room. The 2 sides of the fireplace in the dining room kept it warm on cool days. It, the Great HaNl and the porches, they tell us, were the hub of relaxing and visiting for the guests.

## DESCRIPTION (Continued)

Roof Type: (Gable, Gambrel, Mansard, Flat, Hipped, Combination)

Roof Covering: (Wood shingle, Asphalt, Tile, Metal, Slate)

Roof Trim: (Cornices, bargeboard, brackets, etc.)

Porches: Front (type and description) Roof slant matches gable roof of house; porch extends across front and east side. All materials are heart pine, including (8) 12 foot turned posts, the turned balusters and rails in between, newell posts, flooring and beaded ceiling.

Rear (type and description) This porchvis one year old. It is of deck type and replaces a concrete stoop (original type of steps unknown). Iron inserts in the rail are from the Old Wells Street Bridge in Chicago.

Side (type and description) \_\_\_\_ Same as front.

Doors: Main entrance (location, description) Large heart pine glass-paned door with transom above, flanked with large windows which form surround, opens to Great Hall.

Other entrances (location, description) 1) opens to dining room from front porch; 2) door opens into kitchen from side porch; 3) door with stained glass surround opens between breakfast/sun room and back porch.

Windows: Types and number of each floor of facade Front: 3 on lower level, 2 dormers above. East side: 5 lower level, 4 above. Back: 3 windows, 2 stained glass windows plus stained glass surroundTypesowan hamble fewirdows represented by 5 lower level, 2 above. Majority are original and are heart pine, but some have been replaced.

Interior: Describe mantels, stairways, wainscoting, plasterwork and any unusual features. Walls and ceilings are beaded heart yellow pine in all rooms except dining room, kitchen, first floor back bedroom and bath and master bedroom, where they are plaster and wallpaper. All wood has been restored to original finish except in Family Room where it is painted. Floors tongue and groove heart pine. Most woodwork is rare curly pine. Leaded glass French doors in Great Hall. 3-sided fireplace has original curly pine mantle in Great Hall. Doors are solid heart pine with transoms. The ceilings are 13 feet on the first floor, and 10 feet on the second. Two stairwells lead to separate sections of second floor. Most of the gas light piping still remains in walls and ceilings. One of the dining room fireplaces has a rare hand-carved cherry mantle (not original).

Other: Use this space to describe any additions, alterations, outbuildings or other features of the structure and its surroundings. See Site Plan for dimensions. Pump house is on original site but water tower has been removed. Carriage house, on original site, is in the final stages of restoration by owner. Only addition to the house was done in the early 20's (kitchen and back bedroom on first floor and master bedroom area). In areas where house had been "modernized", owners have restored with authentic period pieces -- cherry mantle, stained glass, ceiling fans, lighting fixtures, etc. Extensive termite damage in rear of house was corrected with pine customed milled for breakfast/sun room and back wall of family room (see photo) was corrected with pine customed milled to match original wood. Salvaged wood was used in porch restoration.

On an additional sheet make a sketch of the floor plan of the building, showing dimensions if possible.
THIS IS NOT REQUIRED!

DESCRIPTION	ON (Continued)			
STRUCTURE:	On a separate sheet of paper give a complete as possible verbal description of the structure. (See examples)			
OBJECT:	On a separate sheet of paper give a complete as possible verbal description of the object. (See examples)			
SITE:	On a separate sheet of paper give the present description of the site and how the site is believed to have looked during its period of importance.			
DISTRICT:	On a separate sheet of paper give a general description of the district. Also needed is a numbered list of the structures in the district corresponding to the sketch map. This listing should include a name for the structure, a date of construction, a brief description, a statement of why the structure is significant, if it is.			
*A MAP W	WITH THE LANDMARK MARKED AND PHOTOGRAPHS MUST BE ST	IBMITTED WITH THIS FORM*		
44.444	THE THE PROPERTY OF THE PROPERTY OF THE PROPERTY OF	Walleting Wall Hills 1994		
	A U.S. Geological Survey Map is preferred, but if yone a county highway map may be used.	you are unable to obtain		
Photogra	graphs: Black and white, glossy finish, 5 x 7, or 8	3 x 10, is preferred.		
FORM PREPARI	ARED BY			
Name	Donald W. and Rita H. McNair	Date December 28, 1981		
Address	and in the first	lephone 205-965-7839		
Town	Magnolia Springs			
200				
Organizat.	ation	-		
	na Historical Commission use only			
STAFF COM				
MAP REFER	ERENCE: MAP			
	r. M. Reference			
0. 1.	Zone Easting	Northing		
Thematic	Category			
	ALABAMA REGISTER			

NATIONAL REGISTER Potential

#### STRUCTURE DESCRIPTION

(See Site Plans for dimensions)

The structure is a raised Gulf Coast Cottage, though it is considerably larger than most other structures of this type in the area. It is constructed of materials native to the area at the time. Wood is all yellow heart pine. Walls and floors are two and three layers of pine thickness. Brick is of red found in other early brick of the area and brick mason says it was probably made close to the site. It has a sand base mortar.

The exterior walls are all painted clapboard. During restoration, clapboard was removed from rear of house which had suffered extensive damage. The salvagable wood was used to repair deteriorating spots in the front and on the sides. New clapboard was selected to match the original for the rear. The roof was originally hand-hewn wood shake shingles -- some were uncovered during restoration. The porch extends across the front of the house and down the east side. The ceilings are beaded pine and the flooring heart pine. All posts, balusters, rails and newell posts are original.

The exterior has been restored as authentically as owners could ascertain using photos dating to the early 1900's. A notable example is the front porch roof which had been flattened to look "modern" by a previous owner. Photos were used to measure the pitch and restore to original dimensions.


The house sits approximate 600 feet from the Magnolia River, which can be seen from the porch. It is surrounded by large old live oak trees. It is situated at the beginning of Magnolia Springs well-known arch of Oaks which extend past the structure and down Oak Street.

OAK AVENUE 60'R.O.W.

100

MAGNOLIA RIVER


FIRST FLOOR TILL TILLIA BATH ATRIUM DOORSHLITH (281) BED ( DOME FAMILY ROOM 1014"x 1419 BREALFAST - SUN (ORIGINALLY THE KITCHEN -) Score KITCHE CADDED EN 128 16 BUTLERS PHNIEY 47 × 5 37) LEADED VARIA CLOK'S FROM Orosa HEREI AS ATIMES FIFTED) 74 x 1072 WATH (6 -145) LLAU FORT TUB EXEPHANT TRUXE WATERS ! 3 WAV DINING STANKE SING ANNUE PREPURCE GREAT ROOM HALL (148 31) (14×31) BEDROOM 144 (40)



W

# SECOND FLOOR

(ABOVE KITCHEN AND BACE
BEDEVON THIS ADDITION)
WAS ADDED IN THE EARLY
1920'S AND DOES NOT
CONNECT TO THE OTHERS
SECOND FROM )







Replaced wood wall in family room



South end of dining room



Restored bathroom



Front First Floor Bedroom



Curly pine woodwork



North end of Great Hall



South end of Great Hall



Breakfast/Sun Room features stained glass surround. Walls are customed milled pine.